

25 Mercury Cost Estimate

23-Jul-19

1. Clear out trees and brush for working room:	Backhoe and Operator	875.00
	Laborer and Chainsaw	140.00
2. Demolition and loading:	Backhoe and Operator	875.00
	Laborer hand work	120.00
3. Finish and clean up:	Backhoe and Operator	875.00
	Laborer hand work	120.00
4. Chipper and truck:		280.00
5. 3 - 30 cu. Yds. Open top containers		<u>2,250.00</u>
	Take off 480.00 if building stays.	5,535.00
	Cost taking off H.I.S.I.D.'s part	2,250.00

All work based on three days at seven hours a day if everything goes smoothly.

Conditions needed to perform work:

1. Vehicle must be moved off site.
2. Make sure electric is disconnected.
3. Make sure water is disconnected.
4. Make sure H.I.S.I.D. owns lot. Company policy specifies that we are not allowed on private property.

Safety issues. If employees are required to work in these conditions it is highly recommended that that receive Hepatitis C Shots to protect themselves. Cost of these shots are unknown. I understand that it is a series of three shots for each employee and that it can take up to six months to complete.

General: If building is not going to be taken down, the Skid Steer will have to be used as to be able to get underneath the car port. The estimated cost for this change stays the same. If Skid Steer is not able to get under the car port, then all trash removal will have to be done by hand. Also this work should be done in the winter months to reduce the risk of snake and wasp bites.

